

In the Claims:

Please cancel Claims 5 and 6 and amend Claim 1 as follows:

1. (currently amended) A fluid capture and drainage system for ceiling leaks comprising:

a ceiling panel support grid;

a plurality of ceiling panels mounted on said ceiling panel support grid at least one ceiling panel mounted on said ceiling panel support grid, each of said panel panels having at least one raised section located within said panel and at least one lower section forming a trough;

a wall extending along the periphery of each of said panel panels, said wall having a top edge and a rim extending outwardly and generally perpendicularly from said top edge of said wall and at least one opening formed through said wall, said opening communicating with said trough;

a fitting connected to said at least one opening; ~~and~~

means for draining said trough as fluid collects therein attached to said fitting; and

means interconnecting the fitting of one of said plurality of ceiling panels with the fitting of another of said ceiling panels.

2. (original) The fluid capture and drainage system of Claim 1 further including a plurality of raised sections and a plurality of troughs.

3. (original) The fluid capture and drainage system of Claim 2 wherein said plurality of troughs are in fluid communications with each other.

4. (original) The fluid capture and drainage system of Claim 1 further including a flange extending vertically upwardly from said rim of said wall.

5. (cancelled)

6. (cancelled)